SAFEMAN · STUDENT MODULE

SM-CONST

Construction & Contractors Masterclass

SafeMan™ by Oryx Institute · safeman.oryxinstitute.org

Sector Masterclass · Pass mark 70% · 1 modules

Name _____

Student no. _____ Class _____



info@oryxinstitute.org

WELCOME

SafeMan Construction, Civil & Electrical Contractors Masterclass

SafeMan Construction, Civil & Electrical Contractors Masterclass — Sector Masterclass. This SafeMan course is engineered for corporate audit readiness against: NTA Ref 1929; GN 156; ISO 45001.

REGULATORY DISCLOSURE — READ FIRST

SafeMan™ is a proprietary inter-organizational safety management and operational competency benchmark developed by Oryx Institute (safeman.oryxinstitute.org). Courses are engineered in alignment with ISO 45001:2018, ISO 14001:2015, ISO 31000, ILO-OSH guidelines, and pre-referenced against Namibia Training Authority (NTA) Unit Standards and Namibian Government Notice 156 of 1997 for corporate audit readiness. SafeMan credentials verify industry competency and attendance between organizations and are non-NQA credit-bearing.

Contact: info@oryxinstitute.org

Author: Tangi Iigonda · Institution: Oryx Institute | Oryx Safety Academy

How to use this module pack

Work through the modules in order. Each module states its focus and the key points you are expected to carry into practice. Diagrams referenced as web assets accompany the online reader at safeman.oryxinstitute.org. After the modules, sit the knowledge check: 6 questions, pass mark 70%, closed book.

MODULES

Module 1 — Excavations, lifting & the contractor SHE file

Ground, cranes and paperwork: the three things that decide whether a Namibian site week ends well.

Key points

Excavations: support/shoring or battering by soil class, access ladders every 7.5 m, spoil 1 m back, inspection after rain.

Lifting: registered operators, load charts, exclusion zones, lift plans for tandem/critical lifts, registered lifting tackle with colour-coded inspection.

Contractor SHE file: policy, risk assessments, method statements, appointments, medicals, training records, emergency plan — vetted before mobilization.

Electrical: permit-to-work, isolation and earth, test-before-touch, underground service clearance before digging.

Diagram: /assets/webp/sm-harness.webp

ASSESSMENT

Knowledge check

The closed-book knowledge check draws 6 questions from the bank reproduced in Appendix A. Pass mark 70%. Your SafeMan credential is issued after the knowledge check, and remains valid for 24 months from issue.

APPENDIX A — QUESTION BANK

Knowledge check bank

Q1. Spoil heaps stand back from an excavation edge at least:

A. 10 cm

B. 1 m

C. 5 m

D. No rule

Q2. Ladder access in excavations is placed:

A. Every 25 m

B. Within every 7.5 m of travel for workers

C. One per site

D. Never

Q3. A critical lift requires:

A. A quick call

B. A written lift plan with exclusions and roles

C. Two operators only

D. Nothing special

Q4. Lifting tackle inspection is shown by:

A. Paint

B. Colour-coded tags per inspection period

C. Stickers from the shop

D. Memory

Q5. Before digging near services:

A. Dig carefully

B. Clear and mark underground services and use safe dig practice

C. Use a bigger machine

D. Assume maps are wrong

Q6. The contractor SHE file is vetted:

A. After mobilization

B. Before the contractor mobilizes

C. At project end

D. Only for big firms

Answer key

Q1=B Q2=B Q3=B Q4=B Q5=B Q6=B